



# Project Scheduling Case Study: World Outreach Expansion Project

IEOR 4405: Production Scheduling Final Presentation  
Lina Huang, Taeyoung Choi, Tiger Zuo

**April 27th, 2017**



# Executive Summary

---

- Background Story
  - Goals and Objectives
  - Resource Requirement Overview
  - Work Breakdown Structure
  - PERT Method Overview
  - Activity Overview
- Recommendations & Rationale
  - Option 1: Reschedule
  - Option 2: Crashing
  - Option 3: Reschedule and Crashing
- Contingency Plan and Conclusion

# Background Story

---

- A project manager of American Constructors, Inc (ACI), is working on a construction project at World Outreach Church (WOC) in Murfreesboro, Tennessee.
- The project deadline was pushed to **Dec. 14, 2009** due to unavoidable events
- Initially budgeted as a \$31 million project; however, the project manager is authorized to use an additional \$3 million to expedite the project if necessary

**FRONT OF WOC SEPTEMBER 2009**



# Goals and Objectives

---

- Have the project completed before deadline (Dec. 14, 2009, 81 days in total) to maintain the reputation of the company, **Maximum Makespan of 81 Days**
- Reschedule or Crash tasks to meet the Maximum Makespan Requirement
- No room in timeline for errors or mistakes, need a Contingency Plan if errors occurred

# Resource Requirement Overview


---

- The additional \$3 Million Budget could be used as incentives for the subcontractors to work additional time so that the project could be finished on time or for crashing
- Workers- 10 labourers (carpenters, finishers, cleaners, and operators)  
25 different subcontractors
- Time- we have 81 days until Dec. 14, 2009

# Remaining Constructions


---

As of Sep. 24, 2009, three main sections of the property were still unfinished:



Three sections can be processed in a parallel manner. After the three sections were finished, Cleaning and the Government Documentation and review could start.

# Work Breakdown Structure



# PERT Method Overview

---

Assume processing times are deterministic

- Processing time of  $j$  random with mean  $m_j$  and variance  $s_j^2$ .
- We want to determine the **expected makespan**
- Assume we have
- $p_j^a$  = most optimistic processing time
- $p_j^m$  = most likely processing time (mode)
- $p_j^b$  = most pessimistic processing time

Assume we have:

- $p_j^a$  = most optimistic processing time
- $p_j^m$  = most likely processing time (mode)
- $p_j^b$  = most pessimistic processing time

Estimate expected processing time:

$$\mu_j = \frac{p_j^a + 4p_j^m + p_j^b}{6}$$



- Apply CPM with expected processing times



# Activities from Original Statement- Store/Cafe/Kitchen

Tasks	Duration	Predecessors	Optimistic	Most likely	Pessimistic	Notes
1: Framing, hanging & finish drywall	21-23	None	21	22	23	
2: Hard tile installation	10	1	8	10	12	1 to 2
3: Complete stone columns	5	1	4	5	6	1 to 3
4: Millwork	15-21	None	15	18	21	happening at the same time with 1,2,3
5: Casework	5	4	4	5	6	4 to 5
6: Flooring installation SCK	10	5	8	10	12	5 to 6
7: Glass installation SCK	3	2, 3	3	3	3	could be less than 3// 2,3 to 7
8: Painting SCK	10	7	8	10	12	7 to 8
9: Doors installation & matching hardware SCK	5- 8	6, 8	5	6	8	6,8 to 9
10: M.E.P. SCK	10	6, 8	10	10	10	6,8 to 10

# Node Network and Critical Path for Store/Cafe/Kitchen





**Makespan:  $22+10+3+10+10=55$  Days**

# Activities from Original Statement-Sanctuary

Tasks	Duration	Predecessors	Optimistic	Most likely	Pessimistic	Notes
25: Hanging drywall	16	None	14	16	18	
26: Core drill for the rails	2	None	2	2	2	
27: Rails installation	5	26	4	5	6	
28: Carpeting at seats	15	26	13	15	17	
29: Carpeting at rails	5	27	4	5	6	
30: Wood Panelling, trim and stage work	25	28	22	25	28	
31: Painting	20	36	18	20	22	
32: Seats at Audi	20	33	18	20	22	
33: Seats at Bowl	20	25	18	20	22	
34: Stain floor	5	35	4	5	6	35 to 34
35: Wood stage steps	5	26	4	5	6	26 to 35
36: Carpeting at Bowl	5	None	4	5	6	
37: Doors installation & matching hardware	5- 8	31	5	6	8	30,31,34 to 37
38: Window installation	8	None	7	8	9	
39: Waterproofing	7	25	6	7	8	
40: Insulation	3	39	3	3	3	39 to 40
41: Deck completion	5- 10	40	5	8	10	40 to 41 //speed depends on weather
42: Stairs	10	41	8	10	12	41 to 42// easy to reduce time
43: Aluminum rails installation	5	41	4	5	6	
44: Masonry on the stairs	10	42	4	5	6	42 to 44



# Node Network and Critical Path for Sanctuary





**Makespan:  $2+15+25+20=62$  Days**

# Activities from Original Statement-Lobby


Tasks	Duration	Predecessors	Optimistic	Most likely	Pessimistic	Notes
11: Reception area	10	None	8	10	12	happening together with other millwork, counter only 3 days
12: Hard Ceiling	15	None	13	15	17	
13: Drywall installation	15	None	15	15	15	Cage Drywall
14: Painting for 1/F & 2/F LOBBY	5	11	5	5	5	11,12,13 to 14
15: Put a thin concrete layer	5 -8	11	5	6	8	11 to 15 // speed depends on weather
16: Hard tile in the LOBBY	5	13	5	5	5	could be done by a subcontractor//13 to 16
17: Wood treatment	10	16	8	10	12	16 to 17
18: Flooring installation LOBBY	22 -28	17	22	25	28	17 to 18 // 17&18 could be crashed to 30 days
19: Carpeting	9	16, 18	8	9	10	16,18 to 19
20: Public restroom	9	12	8	9	10	12,13 to 20
21: Glass installation LOBBY	3	12	3	3	3	12 to 21
22: Ceiling tile	5	14	5	5	5	14 to 22
23: Doors installation & matching hardware LOBBY	10	18, 19, 20, 22	8	10	12	18,19,20,22 to 23 // happening together with 23&24
24: M.E.P. LOBBY	10	18, 19, 20, 22	8	10	12	18,19,20,22 to 24

# Node Network and Critical Path for Lobby



**Makespan:  $15+5+10+25+9+10=74$  Days**

# Original Critical Path from Public Record



**Original Makespan:  $15+5+10+25+9+10=74+15=89$  Days--does not meet the requirement of 81 days!**

# Recommendation Overview

---

- Option 1: Reschedule
  - Can we relax some of the precedence requirements given in the original plan ?
- Option 2: Crashing
  - What if the manager does not want to rearrange the tasks?
  - How do we incentivize the subcontractors?
- Option 3: Reschedule + Crashing-Goals and Constraints
  - Ideally we want to optimize the scheduling using both approaches.


# Recommendation-Option 1: Reschedule



- Task 19 (Carpeting)
  - Carpeting areas are first floor, second floor and stairs
  - Carpeting could be completed by own crew

New Makespan:  $15+5+10+25+10+15=80 \leq 81$  Days


# Recommendation-Option 2: Crashing



- Wood Treatment & Flooring installation  
Could be shortened by employing the crew to work overtime
- Doors Installation & MEP
- Carpeting

New Makespan:  $15+5+8+22+8+8+15=81 \leq 81$  days

# Recommendation-Option 3: Reschedule + Crashing



- Hard Tile
  - Hard Tile could be completed by subcontractors
  - Drywall would be working on different parts of the lobby
- Wood Treatment & Flooring installation

**New Makespan:  $15+8+22+9+10+15=79 \leq 81$  days**

# Conclusion

---

**Three proposed options all work better than the original critical path, Project Manager should choose the option according to the change of requirements and preferences**

**Some other alternatives (contingency plan):**

- Reallocate resources: Since the Store/Cafe/Kitchen session is a smaller project and finishes in 55 days, we could recycle their labor to work on lobby project.
- Consider using buffer (“No room in the timeline for errors or mistakes, which would inevitably occur”)

# Appendix A: Contingency Plan

---

- **Internal mobilization**

- Since the bookstore/cafe/kitchen session is a smaller project and finishes in 55 days, we could send their workers to help with the lobby project.
- The manager should definitely focus on using as much resources on the lobby session where the jobs take the longest time.

- **Besides crashing/resequencing activities approach, we can prioritize the more time demanding items**

- They are: flooring installation (18), hard ceiling (12) and drywall installation (13); all three of them take a descending order of time of 22, 15 and 15, respectively.
- Flooring installation: the only premise to start task 18 is to finish task 17 due to the minimum requirements of starting 18 we can simply put first of 18.
- Hard ceiling and drywall both have identical duration, we can prioritize either one to have the same result at the end; the reason to make hard ceiling to go first is to avoid items happen later such as, put a thin concrete layer, hard tile to go smoothly. On the other hand, to prioritize drywall is a preparation step of door installation.

# Appendix B: Construction Site Snapshot

---

THE LOBBY OF WOC SEPTEMBER 2009



Source: Photo provided by American Constructors Inc.

FRONT OF WOC SEPTEMBER 2009



Source: Photo provided by American Constructors Inc.

# Appendix C: Project Memorandum & Warranty Contract

## MEMORANDUM

**AMERICAN**

CONSTRUCTORS

A-381

World Outreach Church  
Close-Out

September 24, 2009

## MEMORANDUM

To: (Name) — (Company)  
From: Tom Grott — Senior Project Manager  
Re: World Outreach Church — Murfreesboro  
Subject: Project Close-Out Requirements

Attached please find a summary of all Close out Manuals, Operation Manuals, Warranties, Guarantees, As-builts, and other items required for close out of the World Outreach Church Project. While there are certain items, such as Final Release of Lien's, General Warranty/Guarantee's, that cannot be completed at this time, there are many items that can and should be prepared immediately and submitted. Examples of items needed immediately that are necessary for our final inspections are as follows:

1. Flame Spread Ratings on all fabrics, carpets, VCT flooring, vinyl or rubber base, acoustical ceiling tile, etc.
2. UL Ratings on fire dampers, fire caulk barriers, insulation, and other items.
3. Field Use and/or As-built drawings for all trades, whose work is complete.

In addition, all operation and maintenance manuals and close out manuals for MP&E trades can be immediately prepared and submitted.

Please review the attached list carefully and begin this process immediately. These items are to be forwarded in *triplicate* to our field office located at (Address) no later than (Date). If you have any further questions concerning this please feel free to contact me.

## GENERAL GUARANTEE AND WARRANTY

### General Guarantee and Warranty

**World Outreach Church**

Murfreesboro, Tennessee 37128

**Job No. A-381**

We hereby guarantee that all work performed and all materials and equipment furnished under this contract are in accordance with the Contract Documents and are free from defects of equipment, materials, or design furnished, or workmanship performed by this Contractor or any of our Subcontractors or Suppliers at any tier.

In accordance with Article 12.2.2 of AIA Document A201, if within one (1) year after the date of Substantial Completion of the \_\_\_\_\_ work or designated portion thereof or within one (1) year after acceptance by the Owner of designated equipment or within such longer period of time as may be prescribed by law or by the terms of any applicable warranty required by the Contract Documents, any of our work is found to be defective or not in accordance with the Contract Documents, we shall correct it promptly after receipt of a written notice from the Owner or his agent to do so unless the Owner has previously given us written acceptance of such conditions.



**COLUMBIA | ENGINEERING**

The Fu Foundation School of Engineering and Applied Science



# Thank you for sharing this special moment with us!

IEOR 4405: Production Scheduling Final Presentation  
Lina Huang, Taeyoung Choi, Tiger Zuo

**April 27th, 2017**



**COLUMBIA | ENGINEERING**

The Fu Foundation School of Engineering and Applied Science